VolkerWessels UK

Plant & Equipment Standard - Loading Shovel

VolkerFitzpatrick	VolkerFitzpatrick-Rail	VolkerRail	VolkerStevin	VolkerHighways	VolkerLaser	VolkerServices
✓	· ✓	n/a	\checkmark	√	\checkmark	n/a

- All Plant is to be inspected prior to first use, by completing the appropriate pre-start check sheet and daily / weekly recorded inspections thereafter
- Daily / weekly inspection records for **site based** plant are to be completed and held in the cab or other suitable location.
- Operators must complete a full induction prior to starting work and evidence of having signed on to the appropriate RAMS / WPP / TBS for the task provided
- Sites must assess the suitability and selection of a Wheeled Loading Shovel for particular tasks and environment. A specific risk assessment must be completed prior to work commencing which can be detailed in the main works risk assessment. This must take account of the ground conditions and inclines on which they are to be used



H09-G11

MANDATORY

Issue no.:	2	Date:	Sep 2023	Parent document:	H09 Working with Plant			
Approved for IMS:		IMS Mana	ager	Document owner:	CR Director	Workspace file:	n/a	Page 1 of 2

Plant & Equipment Standard - Loading Shovel

VolkerFitzpatrick ✓	VolkerFitzpatrick-Rail ✓	VolkerRail n/a	VolkerStevin ✓	VolkerHighways ✓	VolkerLaser ✓	VolkerServices n/a
DESIRABLE						
- Drovinity Warning System (DWS)						

- Proximity Warning System (PWS)
- Impose people exclusion area around plant and operation

VolkerWessels UK

- Dependant on size of machine a visibility assessment must be carried out (Red Stick Test) and a record kept. CCTV may be required
- · Coloured seat belts or overband to improve visibility
- Operator competency test prior to starting on site
- Have passed Drugs and Alcohol test on induction or within 2 years on VW UK site

RISKS	CONTROLS			
 People and plant moving into the loading shovel's operating areas Visibility may be restricted for operators on larger machines Limited visibility if travelling with the bucket raised to high Risk of overturning on inclines soft and uneven surfaces. Refer to manufacturer's instructions 	 People accessing and alighting the machine must use the correct steps, have three points of contact and face the machine Safe and clean access into cab Safe and clean access for refuelling and maintenance No entry into exclusion zone unless signalled by operator - Thumbs Up 			
Clothes snagged on controls prior to release of servo isolator / safety handle	 Automatic Braking Systems are available which stop the machine if obstruction detected 			
Controls can be caught inadvertently if near to safety lever	COSHH assessment for fuels, oils and greases			
• Effect of weather on visibility and working / traffic surfaces				
• Operator falling from the machine when mounting or dismounting. Hand rails and steps must be secure; three points of contact maintained and operator must face the machine				

Note: All persons preparing risk assessments involving plant are encouraged to visit the proposed area of work and to review previous risk assessments undertaken for similar activities and safety alerts.

	Issue no.:	2	Date:	Sep 2023	Parent document:	H09 Working with Plant	109 Working with Plant				
Approved for IMS:		IMS:	IMS Mana	ager	Document owner:	CR Director	Workspace file:	n/a	Page 2 of 2		

H09-G11